

Mac Stewardship DxP Contract Area Map and Slash Disposal Map

Map 01 of 02



Tonasket Ranger District Okanongan-Wenatchee National Forest

Revised Date: 10/6/2022
MWI

1:7,825

Contractor Requirements and Notes:
Temporary Roads are required to be ripped to a depth of 18 inches and seeded, C5.1#, C6.6#
Contractor shall pile landing and decking area slash, C6.74# (Option 2)
Seed and block temporary roads and skid trails. C5.1#, C6.6#
All Slash is to remain in or be returned to Subdivision 043. C6.42#
Pulback is required in all Subdivisions, from fences, water developments, gates and private property. C6.74# (Option 2)
Equipment cleaning will be required unless work occurs during winter conditions. C6.315#, with C6.42#
The only approved water drafting site is Summit Lake T39N R28E Section 8.
All temporary roads will be sprayed for weeds as described in Stewardship Project 003 Noxious Weed Spraying (Attachment B) prior to decommissioning. C5.1#
Roads that access landings with non saw material from Stewardship Project 006 shall remain open for one operating season after completion of this project. Roads scheduled for closure or decommissioning that also access landings associated with this project must be completed after the one operating season or before the end date of this contract, whichever is shorter. C5.1#
Purchaser Operations shall be performed in accordance with the schedule specified in Provision C6.315#

Subdivision Number	Projects within the Subdivision Boundary	Acres	Season Required, C6.315#
015	002, 006	160	Winter
024	002, 006	69	
037	002, 006	135	
043	001	132	
045	002, 006	171	Winter
047	002, 006	114	
051	002, 006	61	
056	002, 006	262	
057	002, 006	112	
061	002, 006	129	Winter
062	002, 006	70	
080	002, 006	118	
081	002, 006	41	
102	002, 006	104	
110	002, 006	130	
111	002, 006	60	Winter
451	002, 006	9	

