

Mt. Hull Stewardship Contract Area Map and Slash Disposal Map



Tonasket Ranger District
Okanogan-Wenatchee National Forest

Date: 8/2/2019

1:7,250

Contractor Requirements and Notes:
Temporary Roads are required to be ripped to a depth of 18 inches and seeded, KT-FT.1.0.1#, KT-GT.6.0#
Contractor shall pile landing and decking area slash, KT-FT.7.4.2#
Seed and block temporary roads and skid trails, KT-FT.1.0.1#, KT-GT.6.0#
All Slash is to remain in or be returned to Payment Units: 063, 078, 078, 086, 841, KT-GT.4.2#
Pulback is required in all Payment Units, KT-GT.7.4.2#
Equipment cleaning will be required unless work occurs during winter conditions, GT.3.5, KT-GT.3.1.5#, KT-GT.4.2#

